6426 BOARD DIPLOMA EXAMINATION MARCH/APRIL - 2019 DIPLOMA IN CIVIL ENGINEERING QUANTITY SURVEYING FOURTH SEMESTER EXAMINATION


Time: 3 Hours Total Marks: 80

PART - A $(3m \times 10 = 30m)$

Note 1:Answer all questions and each question carries 3 marks


2:Answers should be brief and straight to the point and shall not exceed 5 simple sentences

- 1. Define estimate and write any two objects of preparing quantity surveying
- 2. Write the formats for preparation of detailed estimation &abstract estimation
- 3. For a hipped roof shown in the figure below, calculate the following



Note: All dimensions are in mm.


- (a) Length of ridge piece
- (b) Length of common rafters
- (c) Length of eaves board
- 4. The Fig. shown below the plan and section of a compound wall. Calculate the quantity of earthwork excavation for



foundation.[All dimensions in section are in mm] the centre line dimension of the plot is 20mX15m

Page: 1 of 7


- 5. Calculate the quantity of cement required in bags for brick masonary in CM (1:6) using country bricks for 19.5m³ of work, if 0.38 m³ of mortar required for 1m³ of masonary
- 6. Calculate the weight of two legged stirrup of 6mm dia for a simply supported beam of size 300X450mm. Concrete cover at all sides is 40mm and unit weight of rod is 0.23 kg/m
- 7. Find the volume of earth work in an embankment of length 1.5km, top width of road is 3.75m and depth is 2m, side slope 1.5:1
- 8. The elevation of VRCC brace of OHSR shown in the figure below. Calculate the VRCC (1:2:4) brace beam, if the section at mid-span is 45 cm x 65 cm




- 9. Write short notes on Book value
- 10. The cost of a newly constructed building including all provision is Rs 20, 00,000/-. Calculate monthly rent, if the reasonable interest on capital is 10%

Note 1:Answer any five questions and each carries 10 marks

- 2:The answers should be comprehensive and the criteria for valuation is the content but not the length of the answer
- Prepare the detailed estimate for the following items of work from the given 11. Fig (a) Earth work excavation for all column footings
 - (b) P.C.C. (1:4:8) using 40mm H.B.G metal for foundations (under Columns only)
 - (c) R.C.C (1:1.5:3) using H.B.G metal for all column footings



- Prepare the detailed estimate for the following items of work from the plan and section shown in the Fig. below
 - (a) Flooring with polished stones
 - (b) Plastering in CM (1: 4) for external walls including parapet without deductions



Code: C16 C-403

¹³. Prepare the data sheet and calculate the cost of items given below:

- (a) Cement concrete (1:4:8) using 40 mm HBG metal unit—1 m³
- (b) RR masonry in CM (1:6) unit—1m³

Materials and labour required:

CC (1:4:8) using 40 HBG metal—1cu.m RR masonry in CM (1:6)—1 cu.m.

0.92m³ 40 mm HBG metal

0.46m³ Sand

0.115m³ Cement

0.2 nos. Mason

3.2 nos. Mazdoors

LS Sundries

1.1m³ Rough stone

 0.34m^3 CM (1:6)

1.8 nos. Mason

2.8 nos. Mazdoors

LS Sundries

Lead statement of materials:

Sl.No.	Materials	Rate at	Leads(in	Conveyancechanges/km
		source(inRs)	km)	VAL
1	40 mm	500 per m ³	10km	Rs. 2 per km/ m ³
	HBG		GUL	
	metal		10°	
2.	Sand	90 per m ³	& km	Rs. 2 per km/ m ³
3.	Rough	180 per m ³	5 km	Rs. 3 per km/ m ³
	stone	ati ⁴		
4.	Cement	3200 © per	Local —	
		MT ?		

Labour charges:

- (i) Mason first class Rs. 223.00 per day
- (ii) Mason second class Rs. 217.00 per day
- (iii) Mazdoor Rs. 212.00 per day
- (iv) Hand mixing charges of cement mortar Rs. 34·00 per m³

- 14. Prepare the data sheet and calculate the cost for the following items of work.
 - (a) RR masonry with CM (1: 8) unit—1 m³
 - 1.05 m³ Rough stone
 - 0.34 m³ CM (1: 8)
 - 1.8 no. Mason
 - 2.8 nos. Men mazdoor
 - LS Sundries
 - (b) Pointing to RR masonry in CM (1: 5) unit—10 m²
 - 0.09 m³ CM (1: 5)
 - 2.28 nos. Mason
 - 0.5 nos. Men mazdoor
 - 1.1 nos. Women mazdoor
 - LS Sundries

Lead statement of materials:

				0./
Sl.No	Materials	Rate at	Leads(in	Conveyancecharges/km
		source(in	km)	50 V
		Rs)		E.L.
1	Rough	320/ m3	15 km	4.00/m3/Km
	stone			A The
2	Sand	95/ m3	10 km	3·00/ m3/Km
3	Cement	2,500/10	(1 tonne)	At site
		kN		

Labour charges:

Mason Rs 225·00/day

Men mazdoor Rs180·00/day

Women mazdoor Rs 180.00/day


Mixing charges for CM Rs 40.00/m³

15. The ground level along the contour lines of a road are given below.

Chainage in m	A Ole	20	40	60	80	100	120	140	160
G.L in m	30.8	31.25	31.85	32.25	33.00	33.65	34.50	34.85	35.50

The formation level at chainage zero is 32.00 m &having rising gradient of 1 in 120. The transverse slope of the ground is level, calculate the volume of earth work by prismoidal rule

- 16. Prepare the detailed estimate for the cement concrete road of 1.50 km length for the following items of work as shown in the figure below:
 - (i) Wearing coat of CC (1:2:4) with 20 mm size HBG metal 100 mm thick
 - (ii) Base coarse of CC (1:4:8) with 40 mm size HBG metal 150 mm thick.



Prepare the detailed estimate for the following items & 17. slab culvert shown in the figure:

(a) Earth work excavation for foundation for abutments and returns.

(b) CC (1:4:8) for abutment and returns. (c) RCC (1:2:4) for deck slab. R.C.C 1:2:4(0.25m slab thick) 0.25 m thick road metal-R.R. Masonry HALF SECTIONAL ELEVATION 12 m 0.6m 0.9 m SLAB CULVERT PLAN

18. Residential building Construction 12 year ago is situated on plot whose total area is 500m². The plinth area of the building is 300m². The present cost of construction of the building is RS 3,30,00/- and the cost of the land is RS 210/-m². The rate of depreciation for the value of the building is 2%. Calculation to total value of property